

EROSION PREVENTION PLAN

January 5, 2024

Erosion Prevention Plan

1. Prior to the commencement of construction activities, the contractor shall install all erosion and sediment control device as shown on the plan. All erosion control devices shall be maintained in effective condition during construction.
2. The contractor is responsible for the timely installation, inspection, maintenance, and/or replacement of all temporary and permanent erosion control devices to ensure proper operation throughout the life of the project. The contractor is responsible for maintenance of permanent measures until construction of the project is completed or until it is accepted by the owner. The owner is responsible thereafter.
3. It shall be the contractor's responsibility to clean roads, control dust, and take all necessary measures to ensure that the site and all roads be maintained in a mud and dust-free condition at all times throughout the life of the contract. Dust control shall include, but is not limited to, water, calcium chloride, and/or crushed stone or coarse gravel.
4. The contractor shall restore disturbed areas as closely as possible. Areas damaged during construction shall be resodded, reseeded, or otherwise restored to their original state. Trees and other existing vegetation shall be retained wherever feasible.
5. Permanent vegetative cover shall be applied to all disturbed areas that have reached finished grade as soon as possible, but not more than fourteen (14) days after the construction activity in that area has permanently ceased. The recommended permanent seeding dates are April 1 to June 15 and August 15 to October 1.